

New Jersey Department of Transportation  
Division of Local Aid and Economic Development  
Summary of Bids - State Aid

Project: 2010 Paving Program III County Routes 612 & 654		South State Inc. 9 P.O. Box 68 Bridgeton, NJ 08302		Arawak Paving Co. Inc. 7503 Weymouth Rd Hammononton, NJ 08037		Mount Construction 427 S. White Horse Pike Berlin, NJ 08009	
Municipality: Townships of Deerfield & Upper Deerfield		Bridgeton, NJ 08302		Hammononton, NJ 08037		Berlin, NJ 08009	
County: Cumberland County, New Jersey		Bridgeton, NJ 08302		Hammononton, NJ 08037		Berlin, NJ 08009	
ITEM#	DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1	Clearing Site	L.S.	100%	\$20,000.00	\$20,000.00	\$20,000.00	\$20,000.00
2	Silt Fence	L.F.	3,100	\$0.10	\$310.00	\$1.75	\$5,425.00
3	HMA Milling, 3" Or Less	S.Y.	5,021	\$4.00	\$20,084.00	\$3.00	\$15,063.00
4	Hot Mix Asphalt 12.5M64 Surface Course, 2" Thick & Variable Wedge	Ton	7,810	\$59.00	\$460,790.00	\$70.00	\$546,700.00
5	9" x 18" Vertical Concrete Curb	L.F.	1,292	\$19.50	\$25,194.00	\$17.00	\$21,964.00
6	Hot Mix Asphalt 19M64 Base Course, 3" Thick	Ton	3,750	\$59.00	\$221,250.00	\$68.00	\$255,000.00
7	Concrete Driveway, 6" Thick	S.Y.	40	\$70.00	\$2,800.00	\$115.00	\$4,600.00
8	Hot Mix Asphalt Driveway, Variable Thickness	S.Y.	859	\$15.00	\$12,885.00	\$28.00	\$24,052.00
9	Inlet, Type "B"	Unit	12	\$3,000.00	\$36,000.00	\$3,500.00	\$42,000.00
10	Inlet, Type "E"	Unit	7	\$3,100.00	\$21,700.00	\$4,000.00	\$28,000.00
11	Inlet Filter, Type 2	Unit	19	\$25.00	\$475.00	\$65.00	\$1,235.00
12	Flared Guide Rail Terminal	Unit	6	\$1,625.00	\$9,750.00	\$1,625.00	\$9,750.00
13	Riprap Stone Channel Protection, 24" Thick (D50=12")	S.Y.	26	\$85.00	\$2,210.00	\$50.00	\$1,300.00
14	Traffic Stripes, Long Life, Epoxy Resin, 4" Wide	L.F.	39,400	\$0.25	\$9,850.00	\$0.25	\$9,850.00
15	Traffic Markings, 24" Wide, White & Yellow, Thermoplastic	L.F.	135	\$4.00	\$540.00	\$5.00	\$675.00
16	Breakaway Barricade	Unit	12	\$0.01	\$0.12	\$25.00	\$300.00
17	RPW, Mono & Bi-Directional, White, Amber & Blue Lens	Unit	243	\$0.10	\$24.30	\$24.02	\$5,836.86
18	Topsoil, 4" Thick	S.Y.	3,663	\$2.00	\$7,326.00	\$1.00	\$3,663.00
19	Fertilizing And Seeding, Type A-3	S.Y.	3,663	\$0.40	\$1,465.20	\$0.50	\$1,831.50
20	Coarse Aggregate, Size No. 3	Ton	150	\$25.00	\$3,750.00	\$65.00	\$9,750.00
21	Beam Guide Rail	L.F.	740	\$16.25	\$12,025.00	\$17.00	\$12,580.00
22	Removal Of Beam Guide Rail	L.F.	484	\$1.00	\$484.00	\$1.00	\$484.00
23	Traffic Director, Flegger	Hour	64	\$51.60	\$3,302.40	\$51.60	\$3,302.40
24	Construction Signs	S.F.	400	\$10.00	\$4,000.00	\$8.00	\$3,200.00
25	I-4 Soil Aggregate	C.Y.	1,833	\$0.01	\$18.33	\$3.00	\$5,499.00
26	12" H.D.P.E. Pipe	L.F.	40	\$50.00	\$2,000.00	\$60.00	\$2,400.00
27	Dense Graded Aggregated, 6" Thick	S.Y.	18,264	\$6.00	\$109,584.00	\$7.75	\$141,546.00
28	18" H.D.P.E. Pipe	L.F.	148	\$50.00	\$7,400.00	\$70.00	\$10,360.00
29	Asphalt Price Adjustment	L.S.	100%	\$65,000.00	\$65,000.00	\$65,000.00	\$65,000.00
30	Roadway Excavation, Unclassified	C.Y.	7,656	\$1.55	\$11,866.80	\$5.00	\$38,280.00
31	Nonvegetative Surface, Hot Mix Asphalt	S.Y.	55	\$35.00	\$1,925.00	\$40.00	\$2,200.00
32	Riprap Stone Slope Protection, 12" Thick (D50=6")	S.Y.	145	\$70.00	\$10,150.00	\$80.00	\$11,600.00
33	15" H.D.P.E. Pipe	L.F.	682	\$32.00	\$22,144.00	\$62.00	\$42,904.00
34	Rumble Strips	Unit	1	\$950.00	\$950.00	\$2,273.07	\$1,200.00
35	Topsoil Stabilization, Type 1 Mat	S.Y.	500	\$1.00	\$500.00	\$2.00	\$1,000.00
36	Stabilization Geotextile	S.Y.	4,000	\$0.15	\$600.00	\$0.50	\$2,000.00
37	Inlet, Type "A"	Unit	1	\$2,000.00	\$2,000.00	\$2,300.00	\$4,000.00
38	24" H.D.P.E. Perforated Pipe, In 4 x 4 Stone Trench	L.F.	351	\$65.00	\$22,815.00	\$85.00	\$29,835.00
39	Inlet, Type "DB"	Unit	1	\$5,000.00	\$5,000.00	\$5,000.00	\$6,000.00
40	24" H.D.P.E. Pipe	L.F.	80	\$70.00	\$5,600.00	\$80.00	\$6,400.00
41	36" H.D.P.E. Pipe	L.F.	20	\$200.00	\$4,000.00	\$115.00	\$2,300.00
42	Fuel Price Adjustment	L.S.	1	\$50,000.00	\$50,000.00	\$50,000.00	\$50,000.00
<b>TOTAL BID=</b>					<b>\$1,197,768.15</b>		<b>\$1,388,000.00</b>

J. Fletcher Creamer & Son, Inc.  
1219 Mays Landing Road  
Folsom, NJ 08037

I hereby certify that this is a true copy of the bids received on **April 21, 2010**.

County Engineer